# ()) Stantec



# MOOSONEE AIRPORT AIRPORT IMPROVEMENTS INCLUDING

RUNWAY & TAXIWAY REHABILITATION TOWN OF MOOSONEE, ONTARIO, CANADA TRANSPORT CANADA AIRPORTS CAPITAL ASSISTANCE PROGRAM

# May, 2016 Project Number: 163301858

Stantec Consulting Services Inc. 1331 Clyde Avenue, Suite 400 Ottawa ON K2C 3G4 Tel. 613.722.4420 www.stantec.com



Aerial and Location Maps NTS






# Drawing List

C-001 C-020 C-050 C-051 C-052 C-053 C-060	1 2 3 4 5 6 7 8	TITLE SHEET GENERAL SITE PLAN SAFETY AND PHASING PLAN LAYOUT PLAN RUNWAY 06–24 LAYOUT PLAN RUNWAY 06–24 LAYOUT PLAN RUNWAY 06–24 LAYOUT PLAN RUNWAY 06–24 LAYOUT PLAN TAXIWAY "A"
C-100	9	GRADING PLAN AND PROFILE RUNWAY 06-24
C-101	10	GRADING PLAN AND PROFILE RUNWAY 06-24
C-102	11	GRADING PLAN AND PROFILE RUNWAY 06-24
C-103	12	GRADING PLAN AND PROFILE RUNWAY 06-24
C-104	13	SPOT GRADE PLAN RUNWAY 06–24
C-105	14	SPOT GRADE PLAN RUNWAY 06–24
C-106	15	SPOT GRADE PLAN RUNWAY 06–24
C-107	16	SPOT GRADE PLAN RUNWAY 06-24
C-110	17	GRADING PLAN AND PROFILE TAXIWAY "A"
C-111	18	SPOT GRADE PLAN TAXIWAY "A"
C-200	19	TYPICAL SECTIONS AND DETAILS
C-300	20	LINE MARKING PLAN
C-301	21	LINE MARKING PLAN
C-303	22	LINE MARKING PLAN
C-400	23	CROSS SECTIONS - 1
C-401	24	CROSS SECTIONS - 2
C-402	25	CROSS SECTIONS - 3
C-403	26	CROSS SECTIONS - 4
C-404	27	CROSS SECTIONS - 5
C-405	28	CROSS SECTIONS – 6





1. REFER TO CONTRACT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

2. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT LOCATIONS AND/OR ELEVATIONS OF EXISTING UTILITIES (ABOVE AND BELOW GRADE) AS SHOWN ON THESE PLANS ARE BASED ON RECORD DRAWINGS AND WERE FIELD SURVEYED FOR CONFIRMATION ONLY WHERE POSSIBLE. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING COMPLETE OR EXACT, AND THE CONTRACTOR SHALL FIELD SURVEY AND VERIFY ALL INFORMATION PRIOR TO COMMENCEMENT OF THE WORK. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES DISCOVERED DURING FIELD VERIFICATION OR DURING CONSTRUCTION.

THE CONTRACTOR SHALL REMOVE ALL DEBRIS IN AND AROUND THE PROJECT AREA, HAUL ROUTES PUBLIC ROADWAYS, THE CONTRACTOR'S STORAGE/STAGING AREA AND OTHER AREAS AS DESIGNATED BY THE MOOSONEE AIRPORT OR THE ENGINEER. DEBRIS REMOVAL SHALL BE CONDUCTED ON A DAILY BASIS OR AT ANY TIME AS REQUESTED BY THE ENGINEER. FAILURE TO COMPLY SHALL RESULT IN A \$1,000 PER DAY FINE UNTIL DEBRIS IS REMOVED TO THE SATISFACTION OF THE ENGINEER AND MOOSONEE AIRPORT OPERATIONS.

4. THE CONTRACTOR'S ACCESS/EGRESS HAUL ROUTES AND WORK AREAS, INCLUDING BUT NOT LIMITED TO THE AIRPORT ROADS, DESIGNATED TRUCK ROUTES, PUBLIC ROADWAYS, VEHICLE ACCESS ROADS, PARKING LOTS, AIRCRAFT APRONS, TAXIWAYS AND SHOULDERS, RUNWAYS, AND OTHER AREAS AS DETERMINED BY MOOSONEE AIRPORT AND/OR THE ENGINEER, SHALL BE MAINTAINED FREE OF FOREIGN OBJECTS AND DEBRIS (FOD) AT ALL TIMES. THE CONTRACTOR SHALL PROVIDE AND OPERATE A SINGLE VACUUM ASSISTED SWEEPER DURING ALL HOURS OF WORK.

5. THE CONTRACTOR SHALL PHOTOGRAPH/VIDEO THE ENTIRE SITE, INCLUDING BUT NOT LIMITED TO STAGING AREAS, HAUL ROUTES, AND THE AIRPORT ACCESS ROADS TO PROVIDE DOCUMENTATION OF PRE-CONSTRUCTION SITE CONDITIONS. COPIES OF THE PHOTOGRAPH AND VIDEO SHALL BE PROVIDED TO THE AIRPORT MANAGER AND ENGINEER. AT THE COMPLETION OF CONSTRUCTION, ALL STAGING AREAS, HAUL ROUTES, AIRPORT ACCESS ROADS AND ANY OTHER AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RETURNED TO THEIR PRE-PROJECT CONDITION BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER. THIS SHALL INCLUDE AT A MINIMUM, REPAIR OF EXISTING GRAVEL/PAVED ROADWAYS, SCARIFYING, TOPSOILING, SEEDING AND MULCHING ANY DISTURBED TURF AREAS, AND SWEEPING OF ALL PAVED SURFACES UTILIZED TO REMOVE CONSTRUCTION MATERIALS AND DEBRIS THAT WERE LOST DURING TRANSIT. THERE IS NO SEPARATE PAY ITEM FOR HAUL ROUTES OR STABILIZED CONSTRUCTION EXITS. ALL WORK ASSOCIATED WITH CONSTRUCTING, MAINTAINING, AND RESTORING HAUL ROUTES AND ADJACENT AREAS IS CONSIDERED INCIDENTAL TO THE OVERALL PROJECT.

6. PRIOR TO THE COMMENCEMENT OF THE PROJECT, THE CONTRACTOR'S PERSONNEL SHALL ATTEND A FOREIGN OBJECT DEBRIS (FOD) BRIEFING PRESENTED BY MOOSONEE AIRPORT OPERATIONS. ALL ATTENDEES WILL BE REQUIRED TO UNDERSTAND AND COMPLY WITH ALL MOOSONEE AIRPORT SAFETY AND REQUIREMENTS.

7. AT NO TIME SHALL THE CONTRACTOR CROSS ACTIVE RUNWAYS WITHOUT PRIOR COORDINATION WITH MOOSONEE AIRPORT OPERATIONS AND THE ENGINEER. ESCORTING OF CONSTRUCTION PERSONNEL AND EQUIPMENT TO/FROM THE PROJECT SITE WILL BE PROVIDED AND PERFORMED BY AIRPORT PERSONNEL. THE CONTRACTOR SHALL PROCURE RADIOS AS NEEDED FOR HIS OPERATIONS/COMMUNICATIONS OVER THE LIFE OF THE PROJECT

8. RUNWAY CLOSURE MARKERS SHALL BE PROVIDED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING AND MAINTAINING THESE OVER THE LIFE OF THE PROJECT. THIS WORK IS INCIDENTAL TO THE

9. THE CONTRACTOR IS ADVISED THAT ALL RUNWAY CLOSURES, TAXIWAY CLOSURES OR CAUTIONS ARE SUBJECT TO WIND/WEATHER CONDITIONS AND ADVANCE APPROVAL FROM MOOSONEE AIRPORT OPERATIONS AND THE ENGINEER. 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SITE PREPARATION AS REQUIRED TO ESTABLISH A SUITABLE WORK STAGING AREA. THE CONTRACTOR SHALL RESTORE THE SITE TO ITS ORIGINAL CONDITION AT THE CONCLUSION

11. PRIOR TO THE COMMENCEMENT OF THE PROJECT, THE CONTRACTOR SHALL SUBMIT TO MOOSONEE AIRPORT OPERATIONS AND THE ENGINEER A DETAILED SAFETY PLAN INCLUDING ALL VEHICLE CROSSING LOCATIONS, BARRICADE PLACEMENT, AND CONSTRUCTION ACTIVITIES ON AND ADJACENT TO AIRCRAFT OPERATIONAL AREAS. THE SAFETY PLAN SHALL BE MODIFIED AND UPDATED ON A WEEKLY BASIS BY THE CONTRACTOR TO ADDRESS EACH

12. MATERIAL DELIVERIES AND CONTRACTOR'S ACCESS TO THE PROJECT AREA SHALL BE THROUGH THE GATE SHOWN ON THE PLANS. ALL PERSONNEL, EQUIPMENT AND MATERIALS REQUIRED TO COMPLETE THE PROJECT WILL ACCESS THE

13. STOCKPILES OF EXCAVATED MATERIALS THAT ARE PROPOSED TO BE RE-USED SHALL BE STOCKPILED WITHIN THE WORK LIMITS AT A LOCATION APPROVED BY THE ENGINEER AND MOOSONEE AIRPORT. ALL EXCESS EXCAVATED MATERIAL SHALL BE PLACED, GRADED, COMPACTED AND TOPSOIL AND SEEDED AT THE LOCATION(S) AS DIRECTED BY THE ENGINEER. NO ADDITIONAL COMPENSATION SHALL BE PROVIDED FOR HAULING, STOCKPILING AND REHANDLING OF MATERIALS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.

THE OF UNE			
STRIP RESA STRIP END OF RUNWAY PAVED SURFACE.	06-24		THE OF UP
		MERCE HEGHT UNE	
-	Title GENERAL S	ITE PLAN	
TION PROJECT	Project No. 163301858	Scale AS SHOWN	
DMZ LAB DMZ 16.05.05 Dwn. Chkd. Dsgn. YY.MM.DD	Drawing No. C-010	Sheet 2 of 28	Revision 2

## **GENERAL PHASING NOTES:**

- THE RUNWAY SHALL BE CLOSED FOR A MAXIMUM OF 30 CALENDAR DAYS. • CONTRACTOR MOBILIZATION AND DEMOBILIZATION MAY BE GRANTED IN ADVANCE OF THE
- NOTICE-TO-PROCEED AND AFTER FINAL PROJECT COMPLETION RESPECTIVELY. THESE EFFORTS WILL BE CONSIDERED EXCLUSIVE OF THE 30 CALENDAR DAY RUNWAY CLOSURE PERIOD.
- CONTRACTOR SHALL SCHEDULE MANPOWER AND EQUIPMENT TO ENSURE ALL SCHEDULED WORK CAN BE COMPLETED ENTIRELY WITHIN THE SPECIFIED TIME FRAMES OF EACH PROJECT PHASE.
- SCHEDULING ALL WORK BY THE CONTRACTOR SHALL BE COORDINATED IN WRITING WITH THE ENGINEER A MINIMUM OF 48-HOURS IN ADVANCE OF COMMENCEMENT.
- THE CONTRACTOR SHALL SUBMIT FOR APPROVAL, BY THE ENGINEER, A DETAILED CONSTRUCTION-SITE ACCESS AND MOBILIZATION PLAN WHICH DETAILS LOCATIONS OF SITE ACCESS, CONSTRUCTION VEHICLE MOVEMENT LIMITS, EQUIPMENT/MATERIALS STAGING TEMPORARY CONSTRUCTION SIGNAGE, AND LOCATIONS OF LIGHTED SAFETY BARRICADES/CHANNELIZE CONES.
- THE CONTRACTOR SHALL PROVIDE WORK ZONE AREA LIGHTED CHANNELIZER CONES AND WATER BALLASTED LIGHTED SAFETY BARRICADES AT THE LIMITS OF EACH PHASE OF WORK (REFER TO DETAILS). BARRICADE LAYOUTS FOR EACH PHASE SHALL BE PER THE PHASING PLAN (THIS SHEET). THERE IS NO SEPARATE PAY ITEM FOR FURNISHING, PLACING, MAINTAINING AND REMOVAL OF THESE CONES AND BARRICADES.
- THE LIMITS OF EACH WORK PHASE SHALL BE CLEARLY IDENTIFIED IN THE FIELD PRIOR TO COMMENCEMENT OF EACH PHASE VIA SURVEY FLAGGING AND/OR STAKES TO ENSURE PERSONNEL AND EQUIPMENT DO NOT STRAY INTO ACTIVE AREAS.
- THE CONTRACTOR SHALL CONTINUOUSLY SWEEP ALL PAVEMENTS WITHIN THE WORK AREA AND AIRFIELD HAUL ROUTES TO REMOVE ALL DEBRIS AS REQUIRED AND/OR AS DIRECTED BY THE ENGINEER. PUBLIC ROADS USED BY THE CONTRACTOR TO ACCESS THE SITE DURING CONSTRUCTION SHALL ALSO BE MAINTAINED FREE OF CONSTRUCTION DEBRIS AND MATERIALS. ANY AND ALL LOCAL ROADWAY ORDINANCES AND REGULATIONS SHALL BE OBSERVED BY THE CONTRACTOR IN THEIR ENTIRETY.
- THE CONTRACTOR'S PERSONNEL AND EQUIPMENT SHALL YIELD TO ALL MOVING AIRCRAFT AND EMERGENCY VEHICLES AT ALL TIMES. ALL PERSONNEL WILL BE REQUIRED TO ATTEND AIRSIDE TRAINING CONDUCTED BY THE AIRPORT MANAGER IN ADVANCE OF RECEIVING AUTHORIZATION TO ACCESS THE AIRFIELD.
- NO SMOKING OR OPEN FLAMES WILL BE ALLOWED ON ANY PORTIONS OF THE AIRFIELD AT ANY TIMES. • THE CONTRACTOR SHALL ENSURE THAT NO PAVEMENT LIPS OR EDGES EXCEED 2-INCHES WITHIN THE ACTIVE RUNWAY OR TAXIWAY STRIPS.
- BEFORE ANY CONSTRUCTION EQUIPMENT ENTERS THE AIRFIELD, RUNWAY 06-24 SHALL BE CLOSED TO AIR TRAFFIC, THE RUNWAY 06-24 LIGHTING CIRCUIT SHALL BE DENERGIZED, RUNWAY CLOSURE MARKERS PLACED, LIGHTED CHANNELIZER CONES/BARRICADES PLACED, AND TEMPORARY CONSTRUCTION SIGNAGE INSTALLED. REFER TO INDIVIDUAL PHASING NOTES ON THIS SHEET FOR SPECIFIC REQUIREMENTS AND RESTRICTIONS.
- OTHER THAN AIRFIELD CLOSURES LISTED FOR INDIVIDUAL PHASES, THE AIRPORT SHALL REMAIN FULLY OPERATIONAL AT ALL TIMES. THE CONTRACTOR SHALL ENSURE THAT CONSTRUCTION OPERATIONS DO NO IMPACT ADJACENT AIRCRAFT/AIRPORT OPERATIONS IN ANY FASHION OUTSIDE THE LIMITS OF WORK. THE CONTRACTOR SHALL IMPLEMENT MEASURES TO ENSURE THAT DUST AND AIRBORNE DEBRIS DO NOT DRIFT IN THE DIRECTION OF STATIONARY AND/OR OPERATING AIRCRAFT.


# PHASE I:

### **DURATION:**

- 10 CONSECUTIVE CALENDAR DAYS (DAY 1 THRU 10): WORK HOURS: • 7:00AM TO 7:00PM, SEVEN (7) DAYS PER WEEK **CLOSURES:**
- TAXIWAY A
- RUNWAY 06-24 **DESCRIPTION OF WORK:** • INSTALL RUNWAY CLOSURE MARKERS ON RUNWAY
- PHASE III. • DE-ENERGIZE RUNWAY 06-24 EDGE LIGHTS FOR
- DURATION OF PHASES I THROUGH III. CONES AS REQUIRED.
- RECLAIM, PULVERIZE AND BLEND BITUMINOUS PAVEMENT (APPROX. 44,000m<sup>2</sup>) WITH EXISTING BASE TO A DEPTH OF 300mm. GRADE BLENDED MATERIAL TO MEET DESIGN GRADES AND COMPACT AS SPECIFIED. • REMOVE ALL DEBRIS AND CLEAN WORK AREA.
- CONSTRAINTS: • WORK WITHIN 40m OF RUNWAY 14-32 CENTRELINE SHALL BE COMPLETED UNDER COORDINATION WITH THE AIRPORT AND THE ENGINEER. THIS WORK SHALL BE COMPLETED DURING NON PEAK HOURS. THE CONTRACTOR WILL BE REQUIRED TO PULL BACK FROM THE AREA 15 MINUTES PRIOR TO AIRCRAFT USING THE RUNWAY. THE AIRPORT MANAGER WILL HAVE NOTAMS IN PLACE FOR THIS PROCEDURE. • CONTRACTOR SHALL USE RADIO EQUIPPED ESCORTS
- WHEN CROSSING RUNWAY '14-32'

	PRE-NTP			WE	EEK#	1			-		V	VEEK#	2			-		W	/EEK#	3					٧	VEEK#4	1				POST COMPLETIO
CONTRACT DAYS		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27 2	8 :	29 30	)
PHASE I (10 DAYS) PULVERIZATION & RE-GRADING					PH.	ASE I																									
PHASE II (14 DAYS) PAVING																		PHASE	E												
PHASE III (4 DAYS) LINEMARKING																											PHA	SE III			
FINAL CLEANUP (2 DAYS)																															
DE-MOBILIZATION																															

# PHASE I - PULVERIZE EXISTING PAVEMENT AND RE-GRADE RUNWAY (10 DAYS)





ORIGINAL SHEET - ISO A

# PHASE II:

- 06-24. MARKERS SHALL REMAIN IN PLACE THROUGH
- INSTALL LIGHTED SAFETY BARRICADES AND CHANNELIZER

- **DURATION:** • 14 CONSECUTIVE CALENDAR DAYS (DAY 11 THRU 24): WORK HOURS: • 7:00AM TO 7:00PM, SEVEN (7) DAYS PER WEEK
- CLOSURES: TAXIWAY A
- RUNWAY 06-24 **DESCRIPTION OF WORK:**
- MAINTAIN RUNWAY CLOSURE MARKERS ON RUNWAY 06-24 INSTALLED IN PHASE I. MARKERS SHALL REMAIN IN PLACE THROUGH PHASE III.
- DE-ENERGIZE RUNWAY 06-24 EDGE LIGHTS FOR
- DURATION OF PHASES I THROUGH III. • INSTALL LIGHTED SAFETY BARRICADES AND CHANNELIZER
- CONES AS REQUIRED. • PLACE HOT MIX BITUMINOUS ASPHALT (APPROX. 11,000 TONNES) IN TWO EQUAL LIFTS TO A DEPTH OF 100mm TO MEET DESIGN GRADES AND COMPACT AS SPECIFIED.
- TOPSOIL, SEED ALONG NEW PAVEMENT EDGES. • REMOVE ALL DEBRIS AND CLEAN WORK AREA.
- CONSTRAINTS: • WORK WITHIN 40m OF RUNWAY 14-32 CENTRELINE SHALL BE COMPLETED UNDER COORDINATION WITH THE AIRPORT AND THE ENGINEER. THIS WORK SHALL BE COMPLETED DURING NON PEAK HOURS. THE CONTRACTOR WILL BE REQUIRED TO PULL BACK FROM THE AREA 15 MINUTES PRIOR TO AIRCRAFT USING THE RUNWAY. THE AIRPORT MANAGER WILL HAVE NOTAMS IN PLACE FOR THIS PROCEDURE.
- CONTRACTOR SHALL USE RADIO EQUIPPED ESCORTS WHEN CROSSING RUNWAY '14-32'

# PHASE III:

DURATION:

- 4 CONSECUTIVE CALENDAR DAYS (DAY 25 THRU 28): WORK HOURS:
- 7:00AM TO 7:00PM, SEVEN (7) DAYS PER WEEK CLOSURES: TAXIWAY A
- RUNWAY 06-24
- DESCRIPTION OF WORK: • MAINTAIN RUNWAY CLOSURE MARKERS ON RUNWAY 06-24 INSTALLED IN PHASE I. MARKERS SHALL REMAIN IN PLACE THROUGH PHASE III.
- MAINTAIN LIGHTED SAFETY BARRICADES AND CHANNELIZER
- CONES AS REQUIRED. • PLACE LINEMARKINGS ON RUNWAY AND TAXIWAY
- REMOVE ALL DEBRIS AND CLEAN WORK AREA.
- CONSTRAINTS: • WORK WITHIN 40m OF RUNWAY 14-32 CENTRELINE SHALL BE COMPLETED UNDER COORDINATION WITH THE AIRPORT AND THE ENGINEER. THIS WORK SHALL BE COMPLETED DURING NON PEAK HOURS. THE CONTRACTOR WILL BE REQUIRED TO PULL BACK FROM THE AREA 15 MINUTES PRIOR TO AIRCRAFT USING THE RUNWAY. THE AIRPORT MANAGER WILL HAVE NOTAMS IN PLACE FOR THIS PROCEDURE.
- CONTRACTOR SHALL USE RADIO EQUIPPED ESCORTS WHEN CROSSING RUNWAY '14-32'

### **GENERAL CRITERIA:**

- RUNWAY SAFETY AREA (RSA): 80m WIDE; 40m OFFSET FROM RUNWAY CENTRELINE. ALL PERSONNEL AND CONSTRUCTION EQUIPMENT ARE REQUIRED TO REMAIN OUTSIDE OF THE RUNWAY 14-32 SAFETY AREA AT ALL TIMES
- WHEN RUNWAY 14-32 IS ACTIVE. • RUNWAY STRIP: 150m WIDE: 75m OFFSET FROM RUNWAY CENTRELINE. NO MATERIALS SHALL BE STOCKPILED WITHIN THE RUNWAY 14-32 STRIP AT ANY TIME
- RUNWAY END SAFETY AREA (RESA): 60m WIDE x 150m LONG; 30m OFFSET FROM RUNWAY CENTRELINE. ALL PERSONNEL AND CONSTRUCTION EQUIPMENT ARE REQUIRED TO REMAIN OUTSIDE OF THE RUNWAY 32 RESA AT ALL TIMES.

# PHASE II - PLACE HOT MIX ASPHALT (14 DAYS)





400 - 1331 Clyde Avenue Ottawa ON K2C 3G4 www.stantec.com


The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.


Client/Project MOOSONEE AIRPORT

RUNWAY REHABILITATION PROJECT


MOOSONEE, CANADA


File Name<sup>.</sup>








1952\_scrbgh\_drawing\sheet\_files\163301858\_Moosonee\_Airport\drawing\1952\_scrbgh\_drawing\sheet\_files\163301858c\_050\_054\_layo














V:\01-633\active\163301858\_Moosonee\_Airport\drawing\1952\_scrbgh\_drawing\sheet\_files\163301858c\_100-104\_grading\_pro







ISSUED FOR BID	LAB	МСВ	16.05.16
90% FOR REVIEW	LAB	МСВ	16.04.15
PRELIMINARY - ACAP	LAB	МСВ	15.06.30
Revision	Ву	Appd.	YY.MM.DD












— Strip ——— Str	RIP ——— STRIP ———	STRIP ——— STRIP —	Strip	- Strip	Strip ——	Strip ——	Strip ——	Strip ——	STRIP

					Ц Д										
						10.00									
		· · ·	· — · · -			(TYP	., 	· · · <u> </u>	· · ·						
	8.048	8.051	8.055	8.059	8.062	8.060	8.058	8.056	8.054	8.052	8.050	8.048	8.046	- '8:0 <u>44</u>	8.042
7.99	7.96	7.90	7.95	7.96	7.94	7.98	7.97	7.93	7.96	7.98	7.99	7.99	7.99	7.99	7.98
· 😡	8. <u>1</u> 10	8.114	8.118	8. <u>1</u> 21	8.125	8.123	8. <u>1</u> 21	8.119	8. <u>1</u> 17	8.115	8.113	8. <u>1</u> 11	8.109	8.107	8.105
8.04	8.03	8.03	8.03	8.03	8.02	8.03	8.04	8.00	8.03	8.04	8.05	8.05	8.04	8.04	8.04
	8.173	8.176	8.180	8.184	8.188	8.186	8.184	8.182	8.180	8.178	8.176	8.174	8.172	8.170	8.168
8.09 N	8.08	8.07 N	8.08	8.09 N	8.10	8.09 N	8.10	8.07 N	8.09	8.10 N		8.11 2	8.10	8.09 N	8.10
-8 232	<b>8.235</b> 8.14	8.239	<b>8.243</b> 8.14	<u> </u>	8.250	8.248	8.246	8.244	8.242	<u> </u>	8.238	-8,236	<b>8.234</b> 8.16	<u> </u>	<b>8.230</b> 8.14
8.15 <b>4</b> <b>8.169</b>	8.14	8.11 <b>4</b>	8.14	8.16 <b>4</b>	- 8.18	8.17 <b>4</b>	8.16	8.14 <b>4</b>	8.15	8.16	8.17	8.17 07	8.16	8.14 ت	8.14
8.169	8.173	8.176	8.180	<b>8.184</b>	8.187	8.186	8.183	<sup>4</sup> 8.182	8.179	<b>6</b> - <b>8</b> .177	8.175	8.173	8.171	<b>8.169</b>	8.168
8.10	8.08	8.07	8.10	8.09	8.10	8.11	8.10	8.09	8.09	8.10	8.11	8.11	8.10	8.09	8.11
	8.110	8.114	8.118	8.121	8.125	8.123	8.121	8.119	8.117	8.115	8.113	8.111	8.109	8.107	8.105
8.05	8.03	8.03	8.04	8.03	8.03	8.04	8.04	8.04	8.03	8.04	8.06	8.05	8.04	8.04	8.07
VV	8.048	8.051	8.055	8.059	8.063	8.061	8.059	8.057	8.055	8.053	8.051	8.049	8.046	8.045	8.043
	· <u>z<u>ĝ</u>g</u>	<u> </u>	<u>7.9</u> 9	7.98	7.96	<sup>37.97</sup>	7.98	···	7.97	·7.98 ·	. <del>7 99</del> • •	— Z <sup>9</sup> 9—	<u>7.9</u> 9	7. <u>99</u>	




							( TVP )						—…			
7.973	7.967	7.960	7.954	7.947	7.941	<u> </u>	ں 7.928	<del>. 7.9</del> 21 · —		·	7.902	7.895 🧖	7.889	<u> </u>	7.879	
7.88	7.88	7.88	7.86	7.86	7.84	7.86	7.87	7.86	7.85	7.84	7.83	7.83	7.83	7.83	7.80	
8.036	8.030	8.023	8.017	8.010	8.004	7.997	7.991	7.984	7.978	7.971	7.965	7.958	7.952	7.945	7.941	
7.95	7.94	7.94	7.92	7.92	7.90	7.91	7.92	7.91	7.90	7.90	7.89	7.89	7.88	7.87	7.85	
8.099	8.092	8.086	8.079	8.073	8.066	8.060	8.053	8.047	8.040	8.034	8.027	8.021	8.014	8.008	8.004	
8.01	8.01	8.00 N	7.99	7.98 N	7.97	7.96 N	7.96	7.95 <b>N</b>	7.95	7.95 N	7.95	7.95 N	7.93	7.92 N	7.91	
N 8.161	8.154	<del>8.06</del>	<b>8.141</b> 8.06	-8 135	8.128 8.04		8.116 8.01	8.109	<b>8.00</b>	-8.096	8.089	-8.083	<b>8.076</b> 7.99	- <u>- 8.070</u> 7.97 9	<b>8.066</b> 7.96	
8.08 7	8.06	N	8.06	8.05	8.04	8.02 00	8.01	8.00 <b>00</b>	8.00	8.00 <b>00</b>	8.01	8.01 00	7.99	7.97	7.96	
<b>8.01</b>	8.092	8.086	8.079		8.066	8.060	8.053	<b>4</b> -8.046	8.040	8.00 00 00 8.033	8.027	<b>8.021</b>	8.014	8.008	8.004	
8.01	8.00	7.97	7.98	7.98	7.97	7.96	7.95	7.95	7.95	7.95	7.95	7.95	7.94	7.91	7.89	
8.036	8.030	8.023	8.017	8.010	8.004	7.997	7.991	7.984	7.978	7.971	7.965	7.958	7.952	7.945	7.941	
7.95	7.94	7.92	7.92	7.92	7.90	7.90	7.90	7.89	7.89	7.89	7.89	7.88	7.88	7.86	7.82	
7.974	7.967	7.961	7.954	7.948	7.941	7.935	7.928	7.922	7.915	7.909	7.902	7.896	7.889	7.883	7.879	
7.87 🐞	7.86	7.85	7.85	7.85	7.83	783	• 7.8 <u>4</u>	7.83	7.83	7.83	7.82	7.82 👸	7.81	7.81	7.76	
					/			<u> </u>			• • •	<b>—</b>		🦳 👡	_	








LEGEND	
— RSA —	RUNWAY SAFETY AREA
— TSA —	TAXIWAY SAFETY AREA
	RUNWAY END SAFETY AREA
109.05	EXISTING MINOR CONTOUR
110.25	EXISTING MAJOR CONTOUR
—109.05—	PROPOSED MINOR CONTOUR
—110.25—	PROPOSED MAJOR CONTOUR
	PROPOSED LIMIT OF GRADING
	PROPOSED HOT MIX ASPHALT PAVEMENT
ZZZZ	PROPOSED FULL-DEPTH CRACK REPAIR
	PROPOSED DUCTBANK
нн	PROPOSED HANDHOLE


ION PROJECT	TAXIWAY '	PLAN AND PROFIL 'A'' )0 - 20+285	E
	Project No. 163301858	Scale AS SHOWN	
			Revision




























































9


8




2+340.00

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.







10



10


8








ISSUED FOR BID	LAB	MCB	16.05.16
90% FOR REVIEW	LAB	МСВ	16.04.15
PRELIMINARY - ACAP	LAB	МСВ	15.06.30
Revision	By	Appd.	YY.MM.DE





















The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.





NOT FOR

CONSTRUCTION

5-16-2016









(1:500 H) 0 5 15 20 40 25m (1:50 V) 0 .5 1 1.5 2 2.5m

10

10








	_	
	_	
	_	ISSUED FOR BID
!		90% FOR REVIEW
:		PRELIMINARY - ACAP
· · · · · ·		Revision
	ORIGIN	al sheet <b>- I</b> SO A1


UED FOR BID	LAB	МСВ	16.05.16
% FOR REVIEW	LAB	МСВ	16.04.15
ELIMINARY - ACAP	LAB	МСВ	15.06.30
evision	Ву	Appd.	YY.MM.DD























The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.












(1:500 H) 0 5 15 20 40 25m (1:50 V) 0 .5 1 1.5 2 2.5m








**ISSUED FOR TENDER** NOT FOR CONSTRUCTION 5-16-2016




- 8


0 25 -240.00	5	0	
Title CROSS SECTIONS - 5			
DMZ LAB DMZ 16.05.05 Dwn. Chkd. Dsgn. YY.MM.DD	Project No. 163301858 Drawing No. <b>C-404</b>	Scale AS SHOWN Sheet 27 of 28	Revision 2





Client/Project





(1:500 H) 0 5 15 20 40 25m (1:50 V) 0 .5 1 1.5 2 2.5m

